



Manual 15

Emergency Operations Manual

Issued: July 2021

emergency occurs during a test and Load Shedding is required, the Load Shed Alarm System shall be activated.

NYISO Actions

The NYISO shall perform the following:

1. Initiate the test.
2. Record TO test data and times on form [D-1, Attachment D](#).
3. Forward the test data and times to NYISO Grid Operations Management for review.

Transmission Owner Actions

The TOs shall perform the following:

1. Initiate the test at TO level.
2. Report the following information to the NYISO:
 - System load at time of order
 - Time Load Shedding completed
 - Estimated amount of MW shed

9.3. Test Procedure for Requesting Voltage Reduction

9.3.1. Voltage Reduction test - simulated

At an appropriate time during on peak hours, the NYISO shall initiate a test of Voltage Reduction. The NYISO shall clearly indicate that it is a test and that a Major Emergency does not exist. The NYISO shall use the dialog specified in form [D-2, Attachment D](#).

Upon being notified of the test, the TOs shall proceed through the steps that are normally required if an actual request to implement Voltage Reduction is given, without actually activating any Voltage Reduction devices.

NYISO Actions

The NYISO shall perform the following:

1. Initiate the test.
2. Record TO test data and times on form [D-2, Attachment D](#).

3. Forward the test data and times to NYISO Grid Operations Management for review.

Transmission Owner Actions

The TOs shall perform the following:

1. Initiate the test at TO level.
2. Report the following information to the NYISO:
 - System load at time of order.
 - Time notifications completed.
 - Estimated Load Relief achieved.

9.3.2. Voltage Reduction test - actual

At an appropriate time during on peak hours, the NYISO shall initiate a test of Voltage Reduction. The NYISO shall clearly indicate that it is a test and that a Major Emergency does not exist. The NYISO shall use the dialog specified in form [D-7, Attachment D](#).

Upon being notified of the test, the TOs shall proceed through the steps that are normally required to implement Voltage Reduction, activating the appropriate Voltage Reduction devices.

NYISO Actions

The NYISO shall perform the following:

1. Initiate the test.
2. Record TO test data and times on form [D-7, Attachment D](#).
3. Forward the test data and times to NYISO Grid Operations Management for review.

Transmission Owner Actions

The TOs shall perform the following:

1. Initiate the test at TO level.
2. Report the following information to the NYISO:
 - System load at time of order.
 - Time notifications completed.

- Load Relief achieved.

9.4. Test Procedure for Requesting Emergency Restoration of NYS Power System

At an appropriate time during on peak hours, the NYISO shall initiate a test of Emergency Restoration. The NYISO shall clearly indicate that it is a test and that a Major Emergency does not exist.

Upon being notified of the test, the TOs shall proceed through the steps that are normally required if an actual request to implement Emergency Restoration is given, without actually performing any switching for restoration procedures.

NYISO Actions

The NYISO shall perform the following:

1. Initiate the test.
2. Forward the test data and times to NYISO Grid Operations Management.

NYISO Grid Operations Management shall perform the following actions:

1. Review test data and times with TOs.
2. Issue a report to the NYISO System Operations Advisory Subcommittee (SOAS).

Transmission Owner Actions

The TOs shall perform the following:

1. Initiate the test at TO level.
2. Report the following information to the NYISO:
 - Estimated time to complete restoration.

9.5. Test Procedure for Interim New York Control Area Operation and ACC Operation

At an appropriate time during on peak hours, the NYISO shall initiate a test of Interim NYCA Operation and ACC Operation. The NYISO shall clearly indicate that it is a test and that a Major Emergency does not exist. The NYISO shall use the dialog specified in form [D-5, Attachment D](#).

Upon being notified of the test, the TOs shall proceed through the steps that are normally required if an actual order to implement Interim NYCA Operation & ACC Operation is given.